



www.cejco.net
Phone: 678-377-3100

CEJCO
Carl Eric Johnson, Inc.

Design, Engineering & Fabrication of Fluids Handling Systems
Pumping – Metering – Heating – Cooling – Filtration – Mixing



www.cejco.net
Fax: 678-377-2021

Quote #: 22-0048-R2

Date: July 21, 2021

To: Indian River County
Oslo Plant
1550 9th St SW
Vero Beach, FL 32962

From: Jobi Mathew
CEJCO Services Division
1725 Suite Q MacLeod Drive,
Lawrenceville, GA 30043
Office: 678-377-3100
Fax: 678-377-2021
Cell: 678-371-1973
jmathew@cejco.net

Tank replacement at Oslo Plant WTF Indian River County:

1. **Scope of Installation for Wing Plumbing**
 - Transfer chemicals to temporary tank
 - Provide Crane and other necessary equipment for installation
 - Remove and onsite disposal of existing tank
 - Install new tank onto staging area
 - Install new fill lines, suction lines, sight glasses, vent and restraint system
2. **Polyprocessing 5400 SAFE tank**
 - Additional details on next pages

Tank Price: \$ 45,887.00 for Two (2)

Installation Price: \$ 25,625.00

Estimated Freight: \$ 5,000.00

Delivery: 4-5 weeks after release to fabrication*

*Note: fabrication will begin after final drawing approval and final price approval. Price includes tank, installation & taxes as noted in terms.



www.cejco.net
Phone: 678-377-3100

CEJCO
Carl Eric Johnson, Inc.

Design, Engineering & Fabrication of Fluids Handling Systems
Pumping – Metering – Heating – Cooling – Filtration - Mixing



www.cejco.net
Fax: 678-377-2021

COMPONENTS IN THIS PROPOSAL

While the Tank Offering section above highlights the overall systems, this grid details individual components and accessories for a more complete look.

| LABEL | STOCK# | DESCRIPTION | QTY |
|-------------------------|------------------|---|-----|
| Tank System | | Application: Bulk Tnk Storage of Hypo | |
| Usage: | | 5400Gal Bulk Tnk Storage for Hypo | |
| Chemical: | | Sodium Hypochlorite, 9 - 15%, SPG 1.2 | |
| Op Env: | | Outdoor/To 100F/Wind 3/Seismic 0/Pneumatically Filled>/Non-Scrubber | |
| Nominal_Tank> | | Nominal_Tank> 5400 Safe-tank Inside Primary Tank, Sodium Hypochlorite 9 - | |
| Primary Tank | 42005400441 | 5400 Safe-tank Inside Primary Tank 1.90 specific gravity wall thickness, Crosslinked Polyethylene (XLPE)♦ ,Black Tank wall includes Oxidation Resistance additives(OR1000)♦ | 2 |
| Comments: | | WEIGHT: 1735 DIA: 11'-11" HT: 9'-9" TOP: 24" | |
| Containment: | | Containment Tank | |
| Containment Tank | 42106300411 | 5400 Safe-tank Nested Containment Outside Tank1.90 specific gravity wall thickness, Crosslinked Polyethylene (XLPE)♦ ,Black | 2 |
| Lid/Cover: | | Lid/Cover/Manway | |
| Lid/Manway | 10645 | Cover 24" Manway with 8" vent Combination lid (FS2650 Lid ®)♦ ,Black (polyethylene)with vent screen | 2 |
| Fill/Discharge: | | Fill/Discharge | |
| Fill | 2785 | Universal Ball Dome Fitting 2" Bulkhead fitting Style PVC/EPDM | 2 |
| | 2063 | Flange Adapter 2" Threaded PVC | 2 |
| Dome: | | Dome Fittings | |
| Instrument | 2785 | Universal Ball Dome Fitting 2" Bulkhead fitting Style PVC/EPDM | 4 |
| | 2063 | Flange Adapter 2" Threaded PVC | 4 |
| Sidewall: | | Sidewall Fittings | |
| Inner Tank Fitting | 11449 | BOSS_fitting (Bolted One-piece Sure Seal)♦ 2" This fitting same plastic & compatibility as tank wall- Polyethylene/Titanium/EPDM | 2 |
| Pump Feed | 9753 | Transition Fitting 2" with containment around outlet pipe and built-in flex. PVC/EPDM/Titanium with Expansion Joint PTFE | 2 |
| | 2063 | Flange Adapter 2" Threaded PVC | 2 |
| Venting: | | Venting | |
| Vent | 3275 | U-vent 4" PVC | 2 |
| Level Gauge: | | Level Gauges | |
| Level Measurement | 3356 | Reverse Float Level Gauge♦ PVC | 2 |
| Comments: | | Calibrate Gauge for SPG=1.2 | |
| For Reverse Float Gauge | 2825 | Universal Ball Dome Fitting 2" Flange Style PVC/Titanium/EPDM | 2 |
| | 11633 | Support F/S 7' External Pipe Assembly Blue | 2 |
| | GAL. TAPE 2650 + | Gallonage Tape | 2 |
| Other Parts: | | Other Parts | |



www.cejco.net
Phone: 678-377-3100

CEJCO
Carl Eric Johnson, Inc.

Design, Engineering & Fabrication of Fluids Handling Systems
Pumping – Metering – Heating – Cooling – Filtration – Mixing



www.cejco.net
Fax: 678-377-2021

| | | | |
|------------------|---------|--|---|
| Other Part | NS-140 | Wind Restraints | 2 |
| Services: | | Tests and Services | |
| | BC-008 | Hydro Test | 2 |
| | BC-008 | Impact Test | 2 |
| | BC-008 | Gel Test | 2 |
| | BC-008 | Wall Thickness - Actual | 2 |
| | BC-001 | Approval Drawing | 2 |
| Freight | | Freight and Shipping Summary | |
| Agent: | | Bestway | |
| Method: | | To Be Determined | |
| Payment Method: | | To Be Determined | |
| Source/Name: | | PPC Shipping Department/Jobi Mathew | |
| Contact Info: | | Mike Wyatt;Tel: 772-581-7684 | |
| Freight Estimate | FREIGHT | Freight and Shipping Estimate (Actual TBD) | 1 |
| Comments: | | 1550 9th St SW Vero Beach 32962 | |



www.cejco.net
Phone: 678-377-3100

CEJCO
Carl Eric Johnson, Inc.

Design, Engineering & Fabrication of Fluids Handling Systems
Pumping – Metering – Heating – Cooling – Filtration - Mixing



www.cejco.net
Fax: 678-377-2021

Terms and Conditions:

- Submittal:** Estimated at 2 to 3 business days after purchase order acceptance by CARL ERIC JOHNSON, INC.
- Ships:** Estimated at time as stated above and subject to shop schedule at time of receipt of approved submittal and fulfillment of any contract T&C's
- Freight:** 1) Prepaid and Added to Final Invoice (FOB Lawrenceville, Georgia 30043)
2) Customer Provided 3rd Party Billing Freight Carrier
3) Customer Advised COD
4) Customer Scheduled 3rd Party Shipping Method
- Terms:** 1) NET30 (Subject to Credit Review for New Accounts)
2) Credit card: CEJCO Accepts VISA, MasterCard or American Express (2% surcharge applies on total order on American Express cards)
3) Cash in Advance
- Validity:** 60 Calendar Days from July 21, 2021
- Tax:** Not Included in Proposal
- Spare Parts:** Not Included in Proposal
- Installation:** Included as stated in Proposal
- Startup:** Included as stated in Proposal
- Submittals:** Electronic PDF Included in Proposal - Additional Hard Copies are \$30 Each
- O&M's:** Electronic PDF Included in Proposal - Additional Hard Copies are \$30 Each
- Cancellation Fees:** Cancellation Charges will be assessed at time of cancellation based on project status, restocking fees associated with returning items received or scheduled for delivery before cancellation order is issued
- Warranty:** Products manufactured by Carl Eric Johnson, Inc. are warranted to be free of defects in materials and workmanship for 12 months from date of startup, but not exceeding 18 months from manufacture. Carl Eric Johnson, Inc. assumes liability to replace or repair the product depending on the nature of the warranty claim. Carl Eric Johnson, Inc. will not be liable for any costs of removal, installation, transportation, or any other charges that may arise in connection with a warranty claim. Carl Eric Johnson, Inc. will not be liable for damage or wear to products caused by abnormal operation conditions, accident, abuse, misuse, or if the product was not installed in accordance with Carl Eric Johnson, Inc.'s installation and operating instructions.

Should this proposal become an order, please address and send to:

Carl Eric Johnson, Inc.
1725-Q Macleod Drive
Lawrenceville, GA 30043
Email: jmathew@cejco.net

If you have any additional questions, or require any additional information, please let us know. We appreciate your consideration of our proposal and look forward to the opportunity to work with you further on this project.

Sincerely,
Jobi Mathew P. E.

Carl Eric Johnson, Inc.
1725 Suite Q MacLeod Drive,
Lawrenceville, GA 30043
Office: 678-377-3100
Fax: 678-377-2021
Cell: 678-371-1973
jmathew@cejco.net

Cc via email. R. Leffew, G. Cox, M. Welsh, CEJCO Services