

Date: July 11, 2022

Project: Dick Bird Park Pickleball  
 Vero Beach, FL  
 Ref: 219410

**Quotation Price – Materials Delivered to Job Site and Installation**

**Dick Bird Park**

- (12) Pickleball Courts - 30 footcandles ..... \$ 195,000.00

**All purchase orders should note the following: Clay County RFP 18/19-2**

*Sales tax and bonding are not included.*

*Pricing furnished is effective through February 28, 2023 and is considered confidential.*

Field Description	Quantity	Pricing Per Clay County	Extended Price
Sec IA – Tennis 6 Courts (12 Pickleball)	1 @60%	\$162,400	\$97,440
Sec III – Pole Installation 160mph wind speed, 60’ poles	4	\$5,980	\$23,920
Sec IV B 2 C- Wiring from contactors to poles	500’	\$75	\$37,500
Sec IV B 3 C- Copper Conductors	1500’	\$11.50	\$17,250
Sec IV C- Install of Contactor Cabinet 48”	1	\$5,570	\$5,570
Sec IV D- Surge Arrestor at ECE	4	\$1,200	\$4,800
Sec IV E- Pole Grounding below 70’	4	\$900	\$3,600
Sec V A1- Electrical Engineering	1	\$6,600	\$6,600
Sec V B- Structural Dwgs	1	\$1,350	\$1,350
Sec V F- Project Management	1	\$6,000	\$6,000
<b>Deduct / Design Parameters / Labor</b>			<b>-\$9,030</b>
<b>Total</b>			<b>\$195,000</b>

**Light-Structure System™ with Total Light Control – TLC for LED™ technology**

**Guaranteed Light Performance**

- Guaranteed light levels and uniformity

**System Description**

- Total Light Control™ TLC-LED-900 factory-aimed and assembled luminaires
- Total Light Control™ TLC-LED-600 factory-aimed and assembled luminaires
- (4) Galvanised steel poles
- (4) Pre-cast concrete bases with integrated lightning grounding
- Pole length factory assembled wire harnesses
- Factory wired and tested remote electrical component enclosures
- Enhanced corrosion protection



## Environmental Light Control

- Spill light minimized
- Off-site glare light minimized

## Control Systems and Services

- Control-Link® control and monitoring system to provide remote on/off and dimming (high/medium/low) control and performance monitoring with 24/7 customer support

## Operation and Warranty Services

- Product assurance and warranty program that covers materials and onsite labor, eliminating 100% of your maintenance costs for 25 years
- Support from Musco's Lighting Services Team – over 170 Team members dedicated to operating and maintaining your lighting system – plus a network of 1800+ contractors

## Payment Terms

---

Musco's Credit Department will provide payment terms.

## Delivery Timing

---

8-10 weeks for delivery of materials to the job site from the time of order, submittal approval, and confirmation of order details including voltage, phase, and pole locations.

## Notes

---

Quote is based on:

- Shipment of entire project together to one location.
- 480 Volt, 3 Phase electrical system requirement.
- Owner is responsible for getting electrical power to the site, coordination with the utility, and any power company fees.
- Product assurance and warranty program is contingent upon site review and compatibility with Musco's lighting system
- The owner of the field is responsible for the structural integrity of the existing poles.

Thank you for considering Musco for your lighting needs. Please contact me with any questions or if you need additional details.



Sales Representative  
Musco Sports Lighting, LLC  
Phone: 954-629-8446  
E-mail: [tim.imhoff@musco.com](mailto:tim.imhoff@musco.com)

