

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION
STATE-FUNDED GRANT
SUPPLEMENTAL AGREEMENT

SUPPLEMENTAL NO.

1

CONTRACT NO.

G1U61

FPN

438073-1-54-01

Recipient: Indian River County

This Supplemental Agreement ("Supplemental"), dated _____ arises from the desire to supplement the State-Funded Grant Agreement ("Agreement") entered into and executed on February 11, 2021 as identified above. All provisions in the Agreement and supplements, if any, remain in effect except as expressly modified by this Supplemental.

The parties agree that the Agreement is to be amended and supplemented as follows:

This Supplemental Agreement extends the Term of the Agreement from December 31, 2022 to December 31, 2023.

The first sentence of Paragraph 3 is amended to read as follows:

This agreement shall commence upon full execution by both Parties and the Recipient shall complete the Project on or before December 31, 2023

The deliverables stated in Exhibit A in the original agreement dated February 11, 2021 are hereby deleted and replaced with Exhibit A deliverables of this SA #1.

Reason for this Supplemental and supporting engineering and/or cost analysis:

Due to a Project redesign and material procurement delays, the Deliverables need to be updated and a time extension is needed to provide sufficient time for the contractor to complete the Project before the State Funded Grant Agreement expires.

EXHIBIT A DELIVERABLES

438073-1 69th St from 66th Ave to SR5/US-1 Resurfacing				
Pay Item	Pay Item Description			
101-1	MOBILIZATION/ DEMOBILIZATION	LS		1
102-1	MAINTENANCE OF TRAFFIC	LS		1
104-2	PREVENTION, CONTROL, AND ABATEMENT OF EROSION AND WATER POLLUTION	LS		1
110-1-1	CLEARING & GRUBBING	AC		14
110-7-1	MAIL BOX (F&I)	EA		31
120-1	REGULAR EXCAVATION	CY		8,628
120-6	EMBANKMENT	CY		1,753
160-4	TYPE B STABILIZATION	SY		16,808
210-2A	COQUINA, NEW MATERIAL FOR REWORKING BASE	TN		266
283-1	ASPHALT EMULSION TYPE CSS-1H - PAYMENT WILL BE BASED ON ACTUAL QTY.	GAL		55,000
283-2	CEMENT TYPE 1 OR TYPE 2 - PAYMENT WILL BE BASED ON ACTUAL QTY.	TN		200
283-7	FULL DEPTH BASE RECLAMATION (10" MIXING DEPTH)	SY		19,942
285-706	OPTIONAL BASE GROUP 04 (CEMENTED COQUINA, LBR 100, 6")	SY		13.111
285-716	OPTIONAL BASE GROUP 18 (CEMENTED COQUINA, LBR 100, 16")	SY		1,781
334-1-13A	SUPERPAVE ASPHALT CONCRETE, (SP-12.5) (TRAFFIC C) (1.5")	TN		2,674
334-1-13B	SUPERPAVE ASPHALT CONCRETE, (SP-12.5) (TRAFFIC C) (2")	TN		141
337-7-82	ASPHALTIC CONCRETE FRICTION COURSE (FC-9.5) (TRAFFIC C) (1")	TN		1,781
400-1-2	CONCRETE CLASS I, ENDWALLS	CY		4
425-1-521	INLETS, DT BOT, TYPE C, <10'	EA		12
425-1-551	INLETS, DT BOT, TYPE E, <10' (W/ CONC. APRON)	EA		1
425-2-41	MANHOLE (TYPE 7) (P-BOTTOM) (<10')	EA		1
430-175-115	CONCRETE PIPE CULVERT (15") (S/CD) (CL III)	LF		133
430-175-118A	CONCRETE PIPE CULVERT (18") (S/CD) (CL III)	LF		438
430-175-118B	CORRUGATED ALUMINUM PIPE CULVERT (18") (S/CD)	LF		50
430-175-124A	CONCRETE PIPE CULVERT (24") (S/CD)(CL III)	LF		23
430-964-4	PVC PIPE FOR NON-STANDARD DRAINAGE (10") (SCH 80)	LF		25
430-984-119	MITERED END SECTION (ROUND) (10") (SD)	EA		1
430-984-123	MITERED END SECTION (ROUND) (15") (SD)	EA		3
430-984-125	MITERED END SECTION (ROUND) (18") (SD)	EA		1
520-1-10	CONCRETE CURB AND GUTTER (TYPE F)	LF		412
520-2-4	CONCRETE CURB (TYPE D)	LF		21
520-3	VALLEY GUTTER - CONCRETE (2' WIDE)	LF		110
522-2	CONCRETE SIDEWALK AND DRIVEWAYS (6" THICK) (FIBER REINFORCED)	SY		334
530-3-4	RIPRAP - RUBBLE (F&I) (DITCH LINING)	TN		50

	570-1-1	PERFORMANCE TURF (SOD) (BAHIA)	SY	35,000
**	999-1	ASBUILT SURVEYING AND RECORD DRAWING PREPARATION (BY REGISTERED SURVEYOR)	LS	1
	700-1-11	SINGLE POST SIGN, F&I, GROUND MOUNT, UP TO 12 SF	AS	18
	700-1-13	SINGLE POST SIGN, F&I, GROUND MOUNT, 20-30 SF	AS	1
	700-1-50	SINGLE POST SIGN, RELOCATE	AS	1
	700-13-15	RETROREFLECTIVE SIGN STRIP - F&I, 5'	EA	1
	706-3	RETRO-REFLECTIVE MARKERS	EA	362
	711-11-121	THERMOPLASTIC, STD, WHITE, SOLID, 6"	LF	16,480
	711-11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24"	LF	111
	711-11-141A	THERMOPLASTIC, STD, WHITE, SKIP (6'-10'), 6"	LF	107
	711-11-141B	THERMOPLASTIC, STD, WHITE, SKIP (2'-4'), 6"	LF	200
	711-11-160	THERMOPLASTIC, STD, WHITE, MESSAGE	EA	1
	711-11-221	THERMOPLASTIC, STD, YELLOW, SOLID, 6"	LF	10,696
	711-11-224	THERMOPLASTIC, STD, YELLOW, SOLID, 18"	LF	38
	711-11-231	THERMOPLASTIC, STD, YELLOW, SKIP (10'-30'), 6"	LF	4,020
**	999-1A	UTILITY ASBUILT SURVEYING AND RECORD DRAWING PREPARATION (BY REGISTERED SURVEYOR)	LS	1
**	1050-31-206	UTILITY PIPE (F&I) (PVC) (WATER MAIN) (6")	LF	20
**	1050-31-208	UTILITY PIPE (F&I) (PVC) (WATER MAIN) (8")	LF	31
**	1050-31-212	UTILITY PIPE (F&I) (PVC) (WATER MAIN) (12")	LF	5,919
**	1050-42-214	UTILITY PIPE (F&I) (HDPE, DR 11) (WATER MAIN) (14")	LF	250
**	1055-51-112	UTILITY FITTING (F&I) (45 DEGREE BEND) (WATER MAIN) (12")	EA	20
**	1055-51-206	UTILITY FITTING (F&I) (TEE) (DI) (WATER MAIN) (6"X6")	EA	1
**	1055-51-208	UTILITY FITTING (F&I) (TEE) (DI) (WATER MAIN) (8"X8")	EA	2
**	1055-51-208A	UTILITY FITTING (F&I) (TEE) (DI) (WATER MAIN) (6"X8")	EA	2
**	1055-51-212	UTILITY FITTING (F&I) (TEE) (DI) (WATER MAIN) (6"X12")	EA	2
**	1055-51-212A	UTILITY FITTING (F&I) (TEE) (DI) (WATER MAIN) (8"X12")	EA	4
**	1055-51-308	UTILITY FITTING (F&I) (REDUCER) (DI) (WATER MAIN) (6"X8")	EA	2
**	1055-51-410	UTILITY FITTING - 12"x14" PVC/HDPE TRANSITION COUPLING	EA	2
**	1055-51-508	UTILITY FITTING (F&I) (CAP) (DI) (8") (WATER MAIN)	EA	4
**	1060-11-222A	UTILITY STRUCTURE AND MANHOLE - BELOW GROUND W/ ARV (<80 CF) (9.1'-12')	EA	1
**	1080-11-499	UTILITY FIXTURE (F&I) (TEMPORARY JUMPER CONNECTION) (2")	EA	1
**	1080-24-406	UTILITY FIXTURE (RELOCATE) (VALVE ASSEMBLY) (WATER MAIN) (6")	EA	1
**	1080-24-108	UTILITY FIXTURE (F&I) (VALVE ASSEMBLY) (WATER MAIN) (8")	EA	4
**	1080-24-112	UTILITY FIXTURE (F&I) (VALVE ASSEMBLY) (WATER MAIN) (12")	EA	7
**	1080-32-106	UTILITY FIXTURE (F&I) (SAMPLE POINT) (WATER MAIN) (6")	EA	2
**	1080-32-108	UTILITY FIXTURE (F&I) (SAMPLE POINT) (WATER MAIN) (8")	EA	4

**	1080-32-112	UTILITY FIXTURE (F&I) (SAMPLE POINT) (WATER MAIN) (12")	EA	3
**	1644-136-08	FIRE HYDRANT (F&I) (3 WAY) (2 HOSE, 1 PUMPER) (6")	EA	5
**	999-25	Force Account Roadway		
**	999-25A	Force Account Utility		

** Non-participating Items

CEI CLASSIFICATIONS

SR. PROJECT ENGINEER
PROJECT ADMINISTRATOR

SR. INSPECTOR
INSPECTOR

INSPECTOR'S AIDE

QUALITY CONTROL (QC) MANAGER

EARTHWORK CONSTRUCTION INSPECTOR LEVEL 1

EARTHWORK CONSTRUCTION INSPECTOR LEVEL 2

ASPHALT PAVING TECHNICIAN LEVEL 1

ASPHALT PAVING TECHNICIAN LEVEL 2

CONTRACT SUPPORT SPECIALIST

**STATE-FUNDED GRANT
SUPPLEMENTAL AGREEMENT**

IN WITNESS WHEREOF, the parties have caused these presents to be executed the day and year first above written.

RECIPIENT:

STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

By: _____

Name:

Title:

By: _____

Name: Steven C. Braun, P.E.

Title: Director of Transportation Development

Legal Review:
