

600 St. Road 66 • Sebring, Florida 33875 Tel 863-382-2166 • FAX 863-382-1206 www.tradewindspower.com • www.perkinspower.com Filters Pump Sets Power Units Generator Sets Automatic Engine Controls

TO: Indian River County - Department of Utility Services

1801 27th Street - Building A Vero Beach, Fl. 32960 Tel: (772)-226-1823 Attn: Mr. Jerry Miller imiller@ircgov.com Quotation # PSMW11342Q - 125r3 July 16, 2018

1	Description Model TJ125 Base Awarded Tradewinds Generator Set under FSA contract	Each E 41,173	Extended 41,173
•	No. FSA17-VEH15.0 Spec. No. #71.	11,170	,
	Up-Grade to Model T125-TP-FS Tradewinds Total Pac Generator Set	31,231	31,23
	125 KW (156 KVA) Emergency Standby 277/480 Volts [reconnectable], 60 Hz, Three Phase, 0.8 Power Factor Amp Load Capacity: 188; Load Bank tested.	72,404	72,40
	Perkins Diesel engine, Model 1106D-E66TAG3 TIER 3 @ 1800 RPM complete with 12 Volt Electrics, Radiator & Guard		
	Brushless Single Bearing Alternator with Adjustable Rheostat, Automatic Voltage Regulator & Vibration Isolation Mounts		
	Tradewinds NFPA 110 Digital Instrument/Control Panel with Safety Shutdowns Complete with DC Voltmeter, Hourmeter, Oil and Temperature Gauges Frequency Meter, Ammeter & Voltmeter with Phase Selector Switch, Engine Cool Down Timer, Remote "E" Stop Contacts, Remote Auto Start Control, Low Fuel Level Alarm, Breakers for A/C and D/C, and a Emergency Stop Push Button.		
	Optional Equipment included in above pricing:		
	Battery Rack and Cables Battery Charger installed and wired to duplex electrical box that is wired to incoming service feed with fuses. Stainless Critical Silencer mounted in front of package with vertical discharge Stainless Steel Flex Exhaust Connection Initial fill of oil and antifreeze Water and Oil drain lines with brass ball valves located inside enclosure. Heavy Duty Canister Type Air Cleaner Jacket Water Heater, Thermostatically controlled installed and wired to Duplex electrical box that is wired to incoming service feed with fuses. Step Down Transformer from 480vac - 240vac for generator Battery charger and jacket water heater. 300 gal, Double Wall, UL Approved Subbase Fuel Tank With Leak Detection Mechanical fuel level gauge, low fuel level alarm and sender, internal fuel fill, and all other necessary fittings. Total - Pac Enclosure constructed from a continuous roof, .090 aluminum, White powder coat paint, stainless steel hardware, and keyed alike doors. Generator control panel and Transfer switch controls in single panel A. (1) 200amp, Thompson Open Style Transfer Gen Switch B. (2) 200 amp, Circuit Breaker Type, Service Disconnects Switches, NEMA 4x rated, One mounted on each side of the generator. Full Load Factory test One (1) complete operation and maintenance manual Two (2) year, Standby Warranty		
	Generator total cost: Model 600amp Automatic Transfer Switch Base Award under FSA contract No. FSA17-VEH15.0, Spec #75	4,955	
	Down Grade Generator Model IT301-600-FS Tradewinds Generator Set;	-4,890	
	Delete option - IT301-600-FS. This value is deleted from the awarded switch to determine the net cost per amp for the installation (\$4,955.00 - \$4,890.00 = \$65.00) Installation of transfer switch consists of mounting the transfer switch 15 feet away from main power. Installation of generator power, pour pad, set generator set. Note: If additional compaction is required, services will be quoted separately. Size of quoted automatic transfer switch is 400 amps Total cost for install is determined by multiplying size of ATS x cost per AMP.		
Price Valid	(400 x \$65.00) for install. Permitting fees, fence work, and power company fees are by others.	26,000	
	remitting rees, rence work, and power company rees are by others.	-10,830 15,170	15,17
	Sub Total, FOB our warehouse, Miami, Florida	87,574	87,57
	Onsite Start-up and building load test Delivery to Indian River County, Fl. Curbside	Inc. Inc.	Ind
	Total	87,574	Inc 87,57
	State & Local Tax as Applicable		,
	Estimated Shipping date from receipt of order: 16 - 18 weeks ity: 45 days; 15% Cancellation Charge for Restocking.		
ire-Trans			