

MKI SERVICES, INC.

210 University Drive, Suite 500 ■ Coral Springs, FL 33071 ■ (954) 755-2092 Fax (954) 341-9370.
725 Primera Boulevard, Suite 155 ■ Lake Mary, FL 32746 ■ (407) 805-0063 Fax (407) 805-0062

DATE: 5/14/19
TO: Mr. Richard Meckes
FROM: W. Ben McDorman
SUBJECT: Indian River County West WRF
Hydro GritCleanse™ Installation with Upgrades

Mr. Meckes:

MKI Services, Inc. offers the following described equipment and services under the terms and prices stated in this proposal.

EQUIPMENT

1. One (1) Hydro GritCleanse™
 - o Upgrade of grit cleanse piping and new fluidizing manifold and flow meter
 - o Spare seal and bearing
2. Two (2) Hydro Floatable Spray Systems for each 12-foot diameter Headcell
3. Two (2) Control Panel(s)
 - o Control Panel 1 to control Grit Cleanse
 - o Control Panel 2 to control FOG system and Grit Pump #2

SERVICES

Mechanical Scope Includes:

1. Permanently install GritCleanse™ and remove temporary apparatus
 - a. Move the Hydro GritCleanse™ further into the building so the Discharge Pipe is located directly above the existing Effluent Piping, allowing the dumpster to be located fully inside the building.
 - i. Removal of existing concrete pads and installation of suitable pads for the Hydro GritCleanse™

MKI SERVICES, INC.

- b. Replace the existing PVC spray manifold with stainless steel, including isolation valves and unions for easy removal.
2. Five (5) days of startup services by a Hydro Field Technician

Electrical Scope Includes:

1. Remove One 2007 Control Works panel for control of existing operating HC-pump SC-GS train #1.
2. Retain HD16766 grit cleanse panel to control Grit Cleanse now on train #2
 - a. Install Grit Cleanse panel where existing Control Works panel was.
3. Provide new panel to control:
 - a. FOG systems for headcell on train #1 & train #2.
 - b. Pump for train #2

Items excluded from our erection proposal:

- Permits
- Painting

ACCESS

The basis of this proposal is that it is the responsibility of Indian River County to provide MKI Services with access immediately to the grit removal processes at the facility. Access is to be provided on an uninterrupted basis. Disruptions or work stoppages shall be cause for extra compensation for moving or waiting.

NON-UNION

We are a merit contractor (open shop) and as such will perform all fieldwork with personnel not affiliated with trade unions. The Purchaser is responsible for providing and maintaining site conditions compatible with this labor status.

CONFINED SPACE

By the definitions of confined space in accordance with the OSHA regulations, the subject work is not in a confined space. If Purchaser's safety regulations are in disagreement with this interpretation, then we need to be advised as to what rules will be required and be given an opportunity to price the cost of those rules.

MKI SERVICES, INC.

EXCLUSIONS

Storage
Foundations
Utility supply

PAYMENT TERMS: 90% NET 30 Days, 10% Retainage up to a maximum of 120 days.

SHIPMENT: Shipment can be made 11-13 weeks after receipt of final drawing approval and release for manufacture. All shipments are F.O.B. factory with full freight allowed to the jobsite. All claims for damage or loss during shipment shall be initiated by the purchaser.

SERVICE: Field service is included as specified and called out above.

TAXES: This proposal does not include any sales or use taxes of any kind.


VALIDITY: This proposal is firm for 60 days after which it is subject to withdrawal or change without notice.

INSTALLATION: Installation will require four (4) weeks after all materials are delivered to the jobsite. This quotation is based on one mobilization.

PRICE **\$ 119,325.00**

If you have any questions regarding this scope, please contact me at our Coral Springs office.

Very truly yours,
MKI SERVICES, INC.

A handwritten signature in black ink, appearing to read 'W. Ben McDorman', with a long horizontal line extending to the right.

W. Ben McDorman