

# ATLANTIC ROOFING II

OF VERO BEACH, INC.  
Lic. # CCC1326188

4310 45<sup>th</sup> Street  
Vero Beach, FL 32967

Ph: 772-492-8493 Fax: 772-257-5740 E-Mail: [jerry@atlanticroofing2.com](mailto:jerry@atlanticroofing2.com)

---

Date: 3/8/23

To: Mark Renninger/Richard Meckes

RE: Central Regional WWTP  
3550 49<sup>th</sup> Street  
Vero Beach, FL.

## Building B 1 story section

1. Pressure wash and chlorinate walls.
2. Prepare and detail wall cracks.
3. Saw cut and caulk horizontal cold joints.
4. Caulk window and door perimeters.
5. Apply masonry conditioner at walls.
6. Apply one (1) coat of Sherwin Williams Super Paint with satin finish.

**TOTAL LABOR AND MATERIAL: \$8,990.00**

Authorized Signature: Jerry Malivuk

Date: 3/8/23

# ATLANTIC ROOFING II

OF VERO BEACH, INC.  
Lic. # CCC1326188

4310 45<sup>th</sup> Street  
Vero Beach, FL 32967

Ph: 772-492-8493 Fax: 772-257-5740 E-Mail: [jerry@atlanticroofing2.com](mailto:jerry@atlanticroofing2.com)

---

Date: 3/8/23

To: Mark Renninger/Richard Meckes

RE: Central Regional WWTP  
3550 49<sup>th</sup> Street  
Vero Beach, FL.

## Building B 2 story section

1. Pressure wash and chlorinate walls.
2. Prepare and detail wall cracks.
3. Saw cut and caulk horizontal cold joints.
4. Caulk window and door perimeters.
5. Apply masonry conditioner at walls.
6. Apply one (1) coat of Sherwin Williams Super Paint with satin finish.

**TOTAL LABOR AND MATERIAL: \$20,692.00**

Authorized Signature: Jerry Malivuk

Date: 3/8/23

# ATLANTIC ROOFING II

OF VERO BEACH, INC.  
Lic. # CCC1326188

4310 45<sup>th</sup> Street  
Vero Beach, FL 32967

Ph: 772-492-8493 Fax: 772-257-5740 E-Mail: [jerry@atlanticroofing2.com](mailto:jerry@atlanticroofing2.com)

---

Date: 3/2/23

To: Mark Renninger/Richard Meckes

RE: Central Regional WWTP  
3550 49<sup>th</sup> Street  
Vero Beach, FL.

Plywood and membrane flashings at 2 sides of roof area B3

\*\* Install plywood at these two areas.

\*\* Install Fibertite membrane flashing up and over top of walls.

**TOTAL LABOR AND MATERIAL: \$11,949.00**

**Deduct for stucco remove and replace: \$1,280.00**

**Total: \$10,669.00**

Authorized Signature: Jerry Malivuk

Date: 3/2/23

# ATLANTIC ROOFING II

OF VERO BEACH, INC.  
Lic. # CCC1326188

4310 45<sup>th</sup> Street  
Vero Beach, FL 32967

Ph: 772-492-8493 Fax: 772-257-5740 E-Mail: [jerry@atlanticroofing2.com](mailto:jerry@atlanticroofing2.com)

---

Date: 3/2/23

To: Mark Renninger/Richard Meckes

RE: Central Regional WWTP  
3550 49<sup>th</sup> Street  
Vero Beach, FL.

## Liquid flashing system at wall of roof area C1

- \*\* Remove grates to access back of wall.
- \*\* Clean wall.
- \*\* Install a Fibertite FORTILOCK liquid flashing system.
- \*\* Flashing to go 13" down the back side of wall.
- \*\* Reinstall grates.

**TOTAL LABOR AND MATERIAL: \$8,307.00**

**Deduct for railing: \$1,356.00**

**Total: \$6,951.00**

Authorized Signature: Jerry Malivuk

Date: 3/2/23